

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 34 N.R. 1 W


Cheboygan COUNTY

DESCRIPTION OF CORNER Section corner common to sections 13-14-23-24

CORNER MONUMENT Set 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED August 1966

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

6" W. Pine N 80 W 21.2'

5" R. Maple N 10 W 29.9'

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found during a survey in this township. Found 1" iron bar and fence post in line with old fence west. Falls in line with old road east, check U.S. notes to stream north and fits existing corners west.

SURVEYOR'S SEAL

SIGNED *Kenneth J. Ostling* DATE 11-18-66
REGISTERED LAND SURVEYOR #10068