

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION



LAND CORNER RECORD

T. 34 N.R. 1 W


Cheboygan COUNTY

DESCRIPTION OF CORNER 1/4 corner common to sections 15 - 16

CORNER MONUMENT Set 1" pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED September 66

WITNESSES TO CORNER.....



	6" H. Maple	N 31 W	25.6'
	6" Elm	S 45 E	17.9'
AND	Pipe	N 66 W	6.8'

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set by proportionate measurement between section corners. This point falls about 7.8' SE of Bowen's pipe because of relocation of section corner common to 15-16-21-22, as established by Schaaf and DeLaMater.

SURVEYOR'S SEAL

SIGNED Kenneth J. Osting DATE 11-18-66
REGISTERED LAND SURVEYOR
#10068