

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 34 N.R. 1 W.


Cheboygan COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 31 - 32

CORNER MONUMENT Set 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED August 29, 1962

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

5" Cedar S 51 E 49.6'

5" Cedar N 14 E 23.7'

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found while making a survey in this township. Found 1 1/4 pipe at corner as established by Marcus Schaaf, R. L. S. Sites for both possible U. S. BTs. Falls nearly midpoint on line and checks good with calls of U. S. notes. Considered acceptable as proper location for corner.

SURVEYOR'S SEAL

SIGNED

Kenneth J. Wetling
REGISTERED LAND SURVEYOR

DATE

October 9, 1962