

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 34 NR. 2 W.

Cheboygan

COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 16 and 17

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

14" W. Pine - S13W - 84 1/2 links  
12" W. Pine - N73W - 29 1/2 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by proportionate measurement, midpoint on line, between section corners by Forestry Division survey crew while making a survey in this area. Unable to identify OBTs, although this point falls in a limited area capable of supporting gov't BT species.

Corner was placed and witnessed December 8, 1960

SURVEYORS SEAL

SIGNED

*Kenneth J. Ostling*  
REGISTERED LAND SURVEYOR

DATE 12/23/60