

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 34 NR. 2 W. . . .

Cheboygan

COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 9-10-15-16

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

8" R. Oak	-	S33W	-	39 links
5" W. Pine	-	N22W	-	120½ links
24" Y. Pine stump - East	-		-	44 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restored by Forestry Division survey crew while making a partial retracement of the township. Set corner from stumps of probable government BTs, both Y. Pines in place at correct bearing and distance. Corner checks very good for line and measurement over good 1/4 and section corner west, and to good section corner north and 1/4 corner south. Sufficient evidence for consideration as government corner.

Corner was placed and witnessed December 8, 1960.

SURVEYORS SEAL

SIGNED *Kenneth J. Ostling* DATE 12/23/60  
REGISTERED LAND SURVEYOR