

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T 34 NR 2 W

Cheboygan COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 9 and 10

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

7" B. Oak - N26E - 7 links  
7" B. Oak - S26W - 21 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by proportionate measurement midpoint on line, between section corners by Forestry Division survey crew while making a survey in this township. Unable to identify J. Pine government Bts. Good corners north and south. At least one very old was found in support of this position in the north 1/2 mile of this line.

Corner was placed and witnessed December 8, 1960

SURVEYORS SEAL

SIGNED *Kenneth J. Ostling*  
REGISTERED LAND SURVEYOR

DATE 12/23/60