

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 34 NR. 2 W.

Oneboygan

COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 16-17-20-21

DESCRIPTION OF CORNER MONUMENT 1" pipe with 8" brass cap

WITNESSES TO CORNER

14" Cedar	-	N47W	-	32 links
8" Spruce	-	N63E	-	61½ links
12" Cedar	-	S20E	-	84½ links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while making a survey in this township. Found very old scribed post at corner with remains in place for probable government BTs. Found a large rock buried here also, an unusual occurrence in soil of this swampy nature. Checks measurement north and east. Considered acceptable as proper location for corner.

Corner placed and witnessed December 8, 1960.

SURVEYORS SEAL

SIGNED

Therese J. Ostling
REGISTERED LAND SURVEYOR

DATE 12/23/60