

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION



LAND CORNER RECORD

T. 34 NR. 2 W. ---
T. 35 NR. 2 W. ---

----- Cheboygan ----- COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 5-6-31-32

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap,
6" below surface

WITNESSES TO CORNER -----

14" B. Oak - South - 7½ links

10" B. Oak - N4W - 66½ links

10" J. Pine - N69W - 36½ links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by double proportionate measurement between corners 1 mile north, ½ mile south, 1 mile west, and 3 miles east, by Forestry Division survey crew while making a survey in this township. As was the case at all other corners on this town line, no conclusive evidence of the government survey could be found. DPM was employed to effect the most equitable distribution of lands, and seemed most justifiable in view of the original corner north and good corner south, and in consideration of the total 4 mile measurement on the town line which contains an 8 link per mile over-run. This point also conforms more closely to the record measurement to the stream crossing east.

A 1" iron bar, previously established by unknown, is about 4.93 chains east and some 1.05 chains north. This must be considered erroneous since no support can be found for this location nor does it conform to any pattern of survey.

Corner was placed and witnessed December 2, 1960.

SURVEYORS SEAL

SIGNED *Kenneth J. Oetting* DATE 12/6/60
REGISTERED LAND SURVEYOR