

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 34 NR. 2 W. . .

Cheboygan

COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 15-16-21-22

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 22" B. Pine - S33W - 157 links

7" J. Pine - N70W - 32 links

5" J. Pine - S76E - 28 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restored by Forestry Division survey crew while making a partial retracement of this township. Set monument at fence corner which appears to be located at the government corner as identified by Bowen in 1909. Found Bowen's broken crockery at corner and stumps in place for both government BTs.

Corner was placed and witnessed November 29, 1960.

SURVEYORS SEAL

SIGNED

Kenneth J. Ostling
REGISTERED LAND SURVEYOR

DATE 12/6/60