

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 34 NR 2 W
T 35 NR 2 W

Cheboygan COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 4-5-32-33

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER	7" J. Pine	-	S57E	-	45 links
	8" J. Pine	-	S30W	-	33½ links
	14" J. Pine	-	N23W	-	100½ links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by double proportionate measurement between corners 2 miles east, 2 miles west, 2 miles north and 1 mile south, by Forestry Division survey crew while making a survey in this area. Since no conclusive evidence of the gov't witnesses could be found, it was felt that restoration by DPM produced the most equitable distribution of available lands. This method does, in fact, place the corner in close conformity with the calls of the government record in latitude. Physical features called for in the gov't record were found so grossly incompatible so as to render them useless in fixing any point for longitude along this town line.

A 1" iron bar, previously established by unknown, is about 7.25 chains east and 20 links north, but can find nothing in support of this location, and it was disregarded as obviously in error.

Corner was placed and witnessed December 2, 1960.

SURVEYORS SEAL

SIGNED *Kenneth J. Ostling* DATE 12/5/60
REGISTERED LAND SURVEYOR