

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T<sup>34</sup> NR 2 W  
T 35 NR 2 W

Cheboygan COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 5 and 32

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap,  
6" below surface.

WITNESSES TO CORNER

9" J, Pine - S28E - 54½ links

5" J. Pine - N19E - 20 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by proportionate measurement between section corners by Forestry Division survey crew while making a survey of this area. Set corner midpoint on line between section corners. No government evidence.

Corner was placed and witnessed December 7, 1960.

SURVEYORS SEAL

SIGNED *Kenneth J. Oetting* DATE 12/22/60  
REGISTERED LAND SURVEYOR