

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T 34 NR 2 W  
T 35 NR 2 W

Cheboygan

COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 4 and 33

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

10" J. Pine - N70E - 19 links

24" R. Pine - S14E - 6 1/2 links

Center of road North - 23 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established at midpoint, on line between section corners by Forestry Division survey crew while making a survey in this area. No government evidence. A 1 1/4" pipe is about 5.64 ch east and 9 links south, but this was apparently related to the erroneous section corners on this mile.

Corner was placed and witnessed December 7, 1960.

SURVEYORS SEAL

SIGNED

*Kenneth J. Ostling*  
REGISTERED LAND SURVEYOR

DATE 12/22/60