

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 34 NR. 2 W

Cheboygan COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 3 and 4

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

14" W. Pine - N62W - 58 1/2 links
7" Spruce - N78 1/2 E - 40 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restored by Forestry Division survey crew while making a partial retracement of this township. Set corner from remains of probable government BTs, a Hemlock stump NE, and a Y. Pine stump SW with possible evidence of fade. Found possible evidence of post at corner, also. Hole and tap root for line tree south. Found line blazes 60 years old which follow closely to corrected line. Also, this point conforms very good to the government record random line notes. Original section corner south. This corner is concluded to have adequate support for consideration as the government corner.

Corner was placed and witnessed December 8, 1960.

SURVEYORS SEAL

SIGNED *Kenneth J. Ostling* DATE 12/23/60
REGISTERED LAND SURVEYOR