

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T 34 NR 2 W
T 35 NR 2 W

Cheboygan

COUNTY

DESCRIPTION OF CORNER ~~SEE~~ 1/4 corner common to Sections 3 and 34

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

5" J. Pine - S8E - 69 links

12" J. Pine - N56E - 255 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by proportionate measurement between section corners by Forestry Division survey crew while making a survey in this area. Set corner midpoint, on line between section corners. No government evidence.

Corner was placed and witnessed December 7, 1960.

SURVEYORS SEAL

SIGNED

Walter J. Ostling
REGISTERED LAND SURVEYOR

DATE 12/22/60