

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION



LAND CORNER RECORD

T. 34 NR. 2 ii

Cheboygan

COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 2 and 3

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

9" B. Oak	-	S72E	-	21½ links
10" B. Oak	-	S41W	-	26 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by proportionate measurement between section corners by Forestry Division survey crew while making a survey in this township. Unable to satisfactorily identify government BTs. Corner was set midpoint, on line, between section corners as prescribed by the government record.

Corner was placed and witnessed December 9, 1960.

SURVEYORS SEAL

SIGNED *Kenneth J. Ostling* DATE 12/23/60
REGISTERED LAND SURVEYOR