

*Lancing*

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION



LAND CORNER RECORD

T 34 NR 2 W  
T 35 NR 2 W

Cheboygan COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 3-4-33-34

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 7" J. Pine - S50E - 41 links

6" J. Pine - S30W - 57 links

8" J. Pine - N22E - 83 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by double proportionate measurement between corners  $\frac{1}{2}$  mile south, 1 mile north, 1 mile east, and 3 miles west, by Forestry Division survey crew while making a partial retracement in this area. This method of restoration was considered justified in view of the erratic alignment of the town line. Double proportion adjust the corners on this line to a more acceptable pattern of survey, and conforms more closely to the calls of the government record than the usual single proportion method. Unable to identify any government evidence at this corner, or at any corner along this town boundary within the limits of our survey. A T-iron, previously established by unknown, is about 5.52 chains east and .37 ch north of our corner. Could not relate this iron to any pattern of survey, and considered it obviously in error.

Corner was placed and witnessed December 2, 1960.

SURVEYORS SEAL

SIGNED *Kenneth J. Ostling*  
REGISTERED LAND SURVEYOR

DATE 12/6/60