

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 34 NR. 2 W

Oheboygan COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 3-4-9-10

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

12" R. Pine - N7W - 64 links

6" W. Pine - S89W - 62 links

5" W. Pine - N79E - 44 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division personnel during project work in this area. Restored corner from government BTs, both stumps in place, the SE J. Pine longbutt in place with both faces and some marks. The NW stump tipped out.

Corner was set and witnessed July 19, 1960.

SURVEYORS SEAL

SIGNED *Wesley J. Otting*
REGISTERED LAND SURVEYOR

DATE 8/1/60