

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>34</u> N. <input checked="" type="radio"/> R. <u>2</u> W. <input checked="" type="radio"/>	D-2
2. PROPERTY CONTROLLING IN SECTION <u>5</u>	T. <u>34</u> N. <input checked="" type="radio"/> R. <u>2</u> W. <input checked="" type="radio"/>	5; 8; 9; 12
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. <input type="radio"/> S. <input type="radio"/> R. _____ E. <input type="radio"/> W. <input type="radio"/>	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November 28, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A- Description of original monument and accessories and/or subsequent restoration:

C. (continued)

9	12
Set 5/8" rod w/RLS cap	Set 5/8" rod w/RLS cap & red-top post
12" R. Oak N10°W 38.65	4" W. Pine S52°W 29.15
8" J. Pine N83°W 35.10	5" Maple in clump of 6 N51°W 20.35

B. Description of corner evidence found and or method applied in restoring or re-establishing corner:


- 2 Set at intersection of true 1/4 lines. A 1/2" pipe is located 1.2' S & 0.5' W of proper position.
- 5 Set by standard survey procedure for subdivision of sections.
- 8 Set by standard survey procedure for subdivision of sections.
- 9 Set by standard survey procedure for subdivision of sections.
- 12 Set by standard survey procedure for subdivision of sections. A 3/4" pipe is located 1.5' W of proper location.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-2	5	8
Set 1" pipe w/RLS cap & red-top post	Set 5/8" sq. rod & red-top post	Set 5/8" rod w/RLS cap & red-top post
10" Spruce N86°W 36.9	12" Oak S30°W 18.55	8" J. Pine N21°W 38.84
4" Spruce S32°W 32.2	4" Maple S78°W 22.1	3" J. Pine N17°E 35.6

SIGNED BY *Kenneth J. Ostling* DATE 12/17/77

SURVEYOR'S MICHIGAN REGISTRATION NO. 10068



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ CHEBOYGAN COUNTY