

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 34N R. 3W


Cheboygan COUNTY

DESCRIPTION OF CORNER 1/4 Corner on north side Section 3

CORNER MONUMENT 1" pipe with 1/2" brass cap.

DATE MONUMENT PLACED AND WITNESSED May 31, 1961

WITNESSES TO CORNER.....



6" Jack Pine S 52 E 62.0 ft.

7" Twin Oak S 40 W 87.4 ft.

AND

CIRCLE CORNER REGISTERED

### DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by proportionate measurement, midpoint on line, between section corners, while making a survey in this area.

1/4 corner for Section 34, T35N, R3W, is 45 links west.

SURVEYOR'S SEAL

SIGNED Kenneth J. Ostler DATE May 31, 1961  
REGISTERED LAND SURVEYOR