

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 34 N.R. 3 W


Cheboygan COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 26-27-34-35

CORNER MONUMENT 1" pipe with 4" brass cap

DATE MONUMENT PLACED AND WITNESSED 6/29/61

WITNESSES TO CORNER.....



8" Maple - S58W - 10.5 ft

9" Beech - N75E - 25.1 ft

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while making a survey in this township. Found very old squared stake surrounded by rocks at field corner, in line with fences south and west. One possible BT site approximately in right place. Considered best available evidence.

SURVEYOR'S SEAL

SIGNED *Kenneth J. Ostling* DATE 7/6/61
REGISTERED LAND SURVEYOR