

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 34 N.R. 3 W


Cheboygan COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 27 and 28

CORNER MONUMENT 1" pipe with 4" brass cap

DATE MONUMENT PLACED AND WITNESSED 6/27/61

WITNESSES TO CORNER.....



8" R. Pine - N89E - 24.5 ft

14" Elm - N6E - 24.4 ft

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set by proportionate measurement, midpoint on line, between section corners by Forestry Division survey crew while making a survey in this township. Unable to locate any previous corner. Falls in east ditch of old township road grade and in line with clearing edge west.

SURVEYOR'S SEAL

SIGNED Kenneth J. Ostling DATE 7/5/61
REGISTERED LAND SURVEYOR