

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 34 N. R. 3 W. ●	F-9; <u>G-9</u>
2. PROPERTY CONTROLLING IN SECTION <u>28</u>	T. 34 N. R. 3 W. ●	1; 2
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____	RECORDED PLAT _____	_____
5. PRIVATE CLAIMS _____	_____	_____

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September 7, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- F-9 Set corner by single proportionate measurement, midpoint on line, between section corners. No evidence of previous corner.
 - G-9 Found 5/8" bolt at road intersection, as previously located in 1961 survey in this township.
 - 1 Set by standard survey procedure for subdivision of sections.
 - 2 Set by standard survey procedure for subdivision of sections.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-9	G-9	1
Set DNR Mon. & red-top post	Set DNR Mon. in place of	Set 5/8"x40" Iron Bar w/RLS Cap
4" Basswood S38°E 10.75	5/8" bolt	5" Basswood N66°E 34.15
3" Basswood S09°W 19.85	3" Maple Clstr. N35°W 66.0	3" Maple N25°W 23.15
E-W Trail Rd. North 10	26" Twin Elm S54°W 52.7	
		2
		Set 5/8"x40" Bar w/RLS Cap
		6" Basswood S45°E 1.5
		3" Basswood S41°W 5.65


SIGNED BY Kenneth J. Ostling DATE 11-15-78

SURVEYOR'S MICHIGAN REGISTRATION NO. 10068

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____



SURVEYOR'S MICHIGAN REGISTRATION NO. _____ CHEBOYGAN COUNTY