

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 34 N.R. 3 W


Cheboygan COUNTY

DESCRIPTION OF CORNER 1/4 Corner common to Sections 14 and 15

CORNER MONUMENT 1" pipe with 4" brass cap

DATE MONUMENT PLACED AND WITNESSED 6/27/61

WITNESSES TO CORNER.....



8" B. Oak - S48E - 17.0 ft

9" R. Pine - S78W - 45.1 ft

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set by proportionate measurement, midpoint on line, between section corners, by Forestry Division survey crew while making a survey in this township. Unable to positively identify U.S. B.Ts. A small squared stake is located about 1 chain west of this position but it has no support and appears to be the work of a cruiser, or at best an approximate determination of this corner.

SURVEYOR'S SEAL

SIGNED *Kenneth J. Bething* DATE 7/5/61
REGISTERED LAND SURVEYOR