

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 34 N.R. 3 W


Cheboygan COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 14-15-22-23

CORNER MONUMENT 1" pipe with 4" brass cap

DATE MONUMENT PLACED AND WITNESSED 6/27/61

WITNESSES TO CORNER.....



7" H. Maple - S44E - 32.3 ft

24" Elm - N39W - 31.8 ft

AND

### DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restored by Forestry Division survey crew while making a survey in this area. Restored corner as established by David Bowen in a 1908 survey. Found buried stake surrounded by rocks in line with old township grade south. A 24" Elm which we conclude to be Bowen's NW witness is in place, as well as the site of his SE Beech witness. Measurement of the mile between 14-23 checks Bowen's record to 8 links. This mile is considerably longer than U.S. record, but it should be assumed that County Surveyor Bowen had sufficient support for his location to warrant acceptance in present surveys. This location makes the 2 miles west only 8 links per mile longer than gov't record, and conforms more closely with restored corners north of the Berry Creek road. A concrete monument is located some 248 links east and 18 links north of our position, but cannot determine its origin, and it appears to have been set in line with a fence running south, or else at some arbitrary measurement from section corner 1 mile east. See minutes of Survey for this township for further information.

SURVEYOR'S SEAL

SIGNED Kenneth J. Ostling DATE 7/5/61  
REGISTERED LAND SURVEYOR