

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD


T. 34 N.R. 3 W
T 35 NR 3 W Cheboygan COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 4-5-32-33

CORNER MONUMENT 1" pipe with 4" brass cap

DATE MONUMENT PLACED AND WITNESSED 6/29/61

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

Twin 7" Elm - N36E - 15.5 ft

5" Aspen - N34E - 32.5 ft

AND 5" Ash - S42W - 24.6 ft

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while making a survey in this area. Found a large bolt in place at corner, in line with old E-W fence and road grade south. Checks ok for measurement 2 miles east and to 1/4 corner south and seemed best available evidence. One of a very few corners to be found in this area.

SURVEYOR'S SEAL

SIGNED *Kenneth Dethling* DATE 7/5/61
REGISTERED LAND SURVEYOR