

**SURVEY & REMONUMENTATION**

CHEBOYGAN COUNTY REMONUMENTATION CORNER

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

DEC 29 1994

MAY 03 1995

For corners in  
Cheboygan  
 (County)

**COMMISSION**

Located In:

Corner Code #

RECEIVED FOR RECORD  
 of 12:49 O'Clock P M

*James Spragg*

CLERK/REGISTER  
 CHEBOYGAN COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

- |                                    |                          |            |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey              | T <u>35N</u> R <u>1W</u> | <u>A-4</u> |
|                                    | T _____ R _____          | _____      |
|                                    | T _____ R _____          | _____      |
|                                    | T _____ R _____          | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____  | _____      |
|                                    | S _____ T _____ R _____  | _____      |
| 3. Miscellaneous                   | S _____ T _____ R _____  | _____      |
| Property in Sec.                   | S _____ T _____ R _____  | _____      |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Richard C. Dunn, in a field survey on August, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. John Mullett 1840  
 Set Quarter Section Post  
 10" Beech N58°E 16 Links  
 8" Beech S32°W 6 Links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner Reestablished by single proportionate measurement between corners A-3 and A-6.

*Marvin P. Ross*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-4 Set 5/8" x 30" Iron Rod and 3" aluminum Re-Mon cap and is accepted as a careful and faithful reestablishment of the position of the original corner.  
 8" Poplar N80°E 33.10'  
 10" Maple S20°W 7.35'  
 10" Maple N55°E 12.87'  
 6" Maple N60°W 11.14'

LIGER 010 PAGE 97

Signed by Richard C. Dunn

Date December 15, 1994

Surveyor's Michigan License No. 12020