

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 35 N.R. 1 W


Cheboygan COUNTY

DESCRIPTION OF CORNER Sec. corner common to sections 13, 14, 23 and 24

CORNER MONUMENT Set 1" pipe with 1/4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED October 14, 1965

WITNESSES TO CORNER.....



8" H. Maple - N 70 W - 28.7'

8" H. Maple - S 4 E - 26.2'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established while making a survey in this township. Set this corner at midpoint and on line between corners 1 mile east and 1 mile west. This is on the township centerline and was originally constructed as a straight line and 80 chain miles. Nothing left for USBTs on a previous corner.

SURVEYOR'S SEAL

SIGNED *Kenneth J. Ostling* DATE October 21, 1965  
REGISTERED LAND SURVEYOR #10068