

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD


T. 34 N.R. 1 W  
T. 35 N.R. 1 W Cheboygan COUNTY

DESCRIPTION OF CORNER Sec. corner common to Sections, 2, 3, 34, 35

CORNER MONUMENT Set 1" pipe with 1/4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED July 7, 1965

WITNESSES TO CORNER.....



7" Tamarack N 87 E 83.7'

10" Dead Tan. N 45 W 110.5'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found while making a survey in this township. Found very old post at fence corner in swamp. One very old witness, believed to be NW government BT, down but with good lower face. Checks swamp edges good and fits occupation.

SURVEYOR'S SEAL

SIGNED Reneeth J. Ostling DATE October 18, 1965  
REGISTERED LAND SURVEYOR #10068