

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 35 N.R. 1 W


Cheboygan COUNTY

DESCRIPTION OF CORNER 1/4 corner common to sections 27-28

CORNER MONUMENT Set 1" pipe with 1/4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED June 16, 1966

WITNESSES TO CORNER.....



5" Cedar N 10 W 17.8'

6" Cedar S 10 E 11.4'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found while making a retracement in this township. Found old squared post at fence corner as established in old survey. Both USBT stumps in place, the S E down, but with upper face and scribe marks. Very good original corner.

SURVEYOR'S SEAL

SIGNED Kenneth J. Ostling DATE June 20, 1966
REGISTERED LAND SURVEYOR #10068