

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 35. NR. 2. W. . .

Cheboygan COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 32 and 33

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

7" J. Pine	-	S12W	-	104.4 feet
12" J. Pine	-	S63W	-	119.2 feet

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by proportionate measurement, midpoint on line, between section corners by Forestry Division survey crew while making a survey in this township. Unable to locate anything for government evidence at this corner, but stream crossing north checks very good. An iron bar, previously established by unknown is some 50 links south and about 4 or 5 chains east, but this was apparently set on the basis of the erroneous section corner south.

Corner was placed and witnessed December 7, 1960.

SURVEYORS SEAL

SIGNED Kenneth J. Osting DATE 12/22/60
REGISTERED LAND SURVEYOR