

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 35 NR. 2 W.

Cheboygan

COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 33 and 34

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

14" B. Oak - S45E - 17 1/2 links

12" B. Oak - N2W - 124 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by proportionate measurement, midpoint on line, between section corners by Forestry Division survey crew while making a survey in this township. Nothing left for J. pine BTs, but corner checks very good to stream crossing south.

Corner was placed and witnessed December 8, 1960.

SURVEYORS SEAL

SIGNED Kenneth J. Ostling DATE 12/23/60
REGISTERED LAND SURVEYOR