

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 35 NR. 2 W

Cheboygan COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 28-29-32-33

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

7" J. Pine	-	N37½E	-	49 links
10" J. Pine	-	N38W	-	65½ links
5" B. Oak	-	S83W	-	68½ links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by Forestry Division survey crew while making a survey in this township. Set corner by double proportionate measurement between corners 1 mile north, 2 miles south, ½ mile east and ½ mile west. Unable to identify anything for government BTs, but corner checks for line and distance over good 1/4 and section corners both east and west.

Corner was placed and witnessed December 7, 1960.

SURVEYORS SEAL

SIGNED

Kenneth J. Oetting
REGISTERED LAND SURVEYOR

DATE 12/22/60