

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 35 N.R. 2 W


Cheboygan COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 16, 17, 20 and 21

CORNER MONUMENT Set 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED January 27, 1966

WITNESSES TO CORNER.....



8" W. Oak S 70 W 5.8'

8" W. Oak S 61 E 30.0

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found while making a survey of Section 21. Found stain of old post at corner, in proper position as prescribed by location of original survey (1839) corner. BT stumps for "old" corner in place with good faces showing evidence of defacing action. 1852 U.S. Resurvey notes identify location of original corner, so it was possible to restore proper location of new corner (1852).

SURVEYOR'S SEAL

SIGNED *Kenneth J. Ostling* DATE Jan. 28, 1966
REGISTERED LAND SURVEYOR #20068