

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: \_\_\_\_\_ Located In \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 Cheboygan (County)

1. Public Land Survey		T	35N		R	2W	I-1
		T	35N		R	2W	J-1
2. Property Controlling in Section	S	T			R		
	S	T			R		
3. Miscellaneous Property in Section	S	T			R		
	S	T			R		

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

I, Carl T. Kiiskila, in a field survey on February 27, 2002 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1									●	●			
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-1 G.L.O. John Mullet 1840. Set post  
 Wit: Cedar 10 N52°E 7 links  
 Cedar 8" S16°W 7 links  
 Harvey Mullen 1855  
 Wit: Cedar 10 S64°W 26 links  
 W. Pine 12 S81°E 24 links

Liber B, P. 36 Orlando Doyle R.L.S. #7319 October 1968 found 1 1/4" pipe for corner.

Wit: Power Pole N23.5°W 35.95'  
 Anchor Pole N33°E 35.82'  
 2" Cedar S30°E 51.45'

Kenneth J. Ostling R.L.S. # 10068 used this corner in September of 1964 to reestablish the West 1/4 corner of section 2. Type of monument and witnesses were not given.

J-1 G.L.O. John Mullet 1840  
 Set quarter section post  
 Wit: Pine 20 N77°W 47 links  
 Pine 29 N82°E 52 links

Liber B, P. 31 Kenneth R. Larsen filed a corner record for the 1/4 corner common to section 35, T36NR.2W. and section 2, T.35N.R.2W. set by Kenneth J. Ostling from both U.S.B.T. stumps in place. Also found remains of old post bottom at corner. Kenneth J. Ostling set a 1" pipe with 4" aluminum cap in January of 1965.

Wit: 9" Red Oak N65°E 8.6'  
 22" W. Pine Stump N02°W 32.4'

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

I-1 Found a 1 1/4" pipe fitting Kenneth J. Ostling survey in section 2.

J-1 Found a 1" pipe with 4" aluminum cap as set by Kenneth J. Ostling R.L.S. #10068.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-1 Found 1 1/4" pipe, placed 60d nail in center.

Wit: 6" Spruce S55°E 28.29'  
 4" Balsam S54°W 64.91'  
 Anchor Pole N37°E 36.08'  
 P. Pole N20°W 36.13'

J-1 Found DNR monument.

Wit: 6" White Pine N36°E 17.72'  
 28" Oak S50°E 65.02'  
 8" Jack Pine S08°W 22.84'  
 8" White Pine N75°W 24.63'  
 20" W. Pine Stump N03°E 32.4'  
 10" Oak Stump N65°E 8.7'

Signed by: \_\_\_\_\_

Carl T. Kiiskila

Date: \_\_\_\_\_

7-17-02

Surveyor's Michigan License No.: 33981

