

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:  
Cheboygan Located In \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

1. Public Land Survey	T	35N	R	2W	K-1
	T	_____	R	_____	_____
2. Property Controlling in Section	S	T	R	_____	_____
	S	T	R	_____	_____
3. Miscellaneous Property in Section	S	T	R	_____	_____
	S	T	R	_____	_____

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

I, Carl T. Kiiskila, in a field survey on February 27, 2002 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1											●		
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-1 G.L.O. John Mullett 1840  
 Set corner section 35 and 36  
 Wit: Pine 20 N85°W 99 links  
 Pine 8 N37°E 149 links  
 Harvey Mullen 1855  
 Wit: Yellow Pine S73°E 90 links  
 Spruce Pine N14.5°W 247 links

Liber A, Page 358, Dean C. DeLaMater R.L.S. #5778 set 1" pipe with 4" brass cap from one original B.T. still in place in good condition July 1951.

Wit: 8" Aspen N65°W 74 links  
 10" J. Pine S23°W 281 links  
 12" J. Pine S72°E 227 links

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

K-1 Found DNR monument slightly bent from road grading.  
 Set the original department of Conservation brass cap on a new 1" X 48" pipe.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-1 Set 1" pipe with 4" brass cap  
 Wit: 10" Jack Pine N70°W 55.84'  
 6" Jack Pine N16°W 60.05'  
 14" Jack Pine N20°E 101.16'  
 14" Jack Pine S65°E 117.96'



Signed by: Carl T. Kiiskila  
 Surveyor's Michigan License No.: 33981

Date: 7-17-02