

JAN 23 1996

COMMISSION

CHEBOYGAN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in CHEBOYGAN (County)

Located In: Corner Code #

Table with 3 columns: Item description, Located In (T, R, S), and Corner Code # (M-5).

RECEIVED FOR RECORD 95 DEC 26 PM 2:30 [Signature] CLERK/REGISTER CHEBOYGAN COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-L and rows 1-13.

I, RICHARD C. DUNN, in a field survey on AUGUST, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. John Mullett 1840 Set Post Cor. Secs. 12 & 13 24" Pine S14°W 49 Links 10" Pine N74°W 52 Links

Orlando Doyle #7319 May 1953 Fnd. 1" Pipe 30" Oak NE 66.95' 18" Oak SE 39.40' E. Edge of Pvt. West 2.30'

Ronald Bisher #22428 Oct. 1982 Fnd. 1" Pipe 32" Oak N51°E 67.24' 20" Oak S57°E 39.98' P. Pole S38°E 36.84'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Delmer Porter #15410 Oct. 1983 Fnd. 1" Pipe 32" Oak N51°E 67.24' 20" Oak S57°E 39.98' P. Pole S38°E 36.84'

James Granger #16041 Nov. 1987 Fnd. 2" Pipe 10" J Pine N27°E 94.80' 24" Oak N53°E 67.23' 14" Hickory S50°E 40.02' P. Pole S29°E 36.83'



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-5 Found 1" Pipe in Monument Box and is accepted as a careful and faithful reestablishment of the position of the original corner. Placed 5/8" re-rod and remonumentation cap in pipe at accepted position. 36" Oak w/60P N47°E 67.23' 18" Oak w/tag 15410 S60°30'E 40.00' 15" Oak Set PK N73°W 71.82' P. Pole w/60 P N11°E 111.21' C/L U.S. 27 West 13.22'

LIBER 010 PAGE 137

[Signature]

Signed by [Signature]

Date DECEMBER 4, 1995

Surveyor's Michigan License No. 12020

