

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 35N N.R. 3W


Cheboygan COUNTY

DESCRIPTION OF CORNER 1/4 corner, on south side Section 33

CORNER MONUMENT 1" pipe with 4" brass cap

DATE MONUMENT PLACED AND WITNESSED June 1, 1961

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

20" R. Pine N 83 W 13.0 ft.

12" R. Pine N 1 1/4 E 53.6 ft.

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restored by single proportionate measurement between section corners by Forestry Division survey crew while making a survey in this area. Nothing left for government B. T.'s. Checks fair to swamp edge west.

1/4 corner for Section 4, T34N, R3W is 45 links east.

SURVEYOR'S SEAL

SIGNED *Kenneth J. Ostling* DATE June 6, 1961
REGISTERED LAND SURVEYOR