

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 35N N. R. 3W


Cheboygan COUNTY

DESCRIPTION OF CORNER 1/4 Corner on south side Section 34

CORNER MONUMENT 1" pipe with 4" brass cap

DATE MONUMENT PLACED AND WITNESSED May 31, 1961

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

10" R. Oak N 11 W 55.2 ft.

5" R. Oak N 47 E 56.7 ft.

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by proportionate measurement, midpoint on line, between section corners. Gov't B. T's all gone.

1/4 corner for section 3, T34N, R3W is 45 links east.

SURVEYOR'S SEAL

SIGNED Kenneth J. Osting DATE May 31, 1961
REGISTERED LAND SURVEYOR