

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T.36.. NR.1 E..

.....Cheboygan.....COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 1 and 2 .....

DESCRIPTION OF CORNER MONUMENT Left 1 1/4" pipe in place below surface

WITNESSES TO CORNER .....

5" R. Oak - N38E - 25.0 feet  
9" R. Oak - N36W - 22.1 feet

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while making a survey of Section 2. Found 1 1/4" pipe in place below surface of N-S fireline. A large W. Pine stump in place for possible NE government BT. and this point checks good for measurement to high ridge 12.50 ch south as per government record. Checks for measurement north to Section corner.

Corner was witnessed May 26, 1960.

SURVEYORS SEAL

SIGNED *Kenneth J. Oetting*  
REGISTERED LAND SURVEYOR

DATE 6/9/60