

Survey
MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 36 NR. 1 E
T 37 NR 1, E

Cheboygan COUNTY

DESCRIPTION OF CORNER Witness corner to Meander corner between 2-35,
located S86E 50 links from original Meander Corner.
DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

4" Cedar - N10W - 27.9 feet
8" R. Oak - N62E - 31.6 feet

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established as a witness to the government Meander corner by Forestry Division survey crew while making a survey of Section 2. Set this corner on town line, 50 links easterly of original gov't Meander corner, which is marked by an old square post in lake with the SE gov't BT in place with good marks.

Corner was placed and witnessed May 26, 1960.

SURVEYORS SEAL

SIGNED *Kenneth J. Ostling* DATE 6/9/60
REGISTERED LAND SURVEYOR