

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 36 NR. 1 E

Cheboygan COUNTY

DESCRIPTION OF CORNER North 1/8 corner on N-S 1/4 line, Section 2

DESCRIPTION OF CORNER MONUMENT 1"x24" pipe

WITNESSES TO CORNER

6" Beech - S53E - 14.2 feet  
8" Beech - North - 13.5 feet

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by survey procedure by Forestry Division survey crew while making a survey of Section 2. Set corner by proportionate measurement between center 1/4 and North 1/4 corners, using a mean government distance.

Corner was set and witnessed June 3, 1960.

SURVEYORS SEAL

SIGNED *Kenneth J. Ostling* DATE 7/5/60  
REGISTERED LAND SURVEYOR