

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

RECEIVED
FORESTRY SECTION

JAN 27 1965

FILE No. _____

LAND CORNER RECORD

T. 36 N.R. 1 W.


Cheboygan COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 31 - 32

CORNER MONUMENT Set 1" pipe with 4" brass cap

DATE MONUMENT PLACED AND WITNESSED September 2, 1964

WITNESSES TO CORNER.....



18" W. Pine

N 23 W

39.5'

20" R. Pine

S 73 W

57.8'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found while making a survey in this township. Found evidence of original stake bottom from both U.S.B.T. stumps. The SE stump in place with very good face, the NW longbutt down but found evidence of upper face.

Very good original corner.

SURVEYOR'S SEAL

SIGNED

Kenneth J. Pitting
REGISTERED LAND SURVEYOR #10068

DATE

January 20, 1965