

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

RECEIVED
FORESTRY SECTION

JAN 27 1965

FILE No. _____

LAND CORNER RECORD

T. 36 N.R. 2 W.


Cheboygan COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 35 - 36

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED August 28, 1964

WITNESSES TO CORNER.....



14" R. Pine stump N 71 E 28.8'

10" R. Oak S 17 W 34.8'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found while making a survey in this township. Found old post bottom at corner. Both U.S.B.T. stumps in place, the NW with good face. Falls about 2' north of corner fence post.

SURVEYOR'S SEAL

SIGNED *Wm. H. Hobbins* DATE January 20, 1965
REGISTERED LAND SURVEYOR # 10068