

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY:	T. N. S., R. W.	
2. PROPERTY CONTROLLING IN SECTION: 24	T. 36 N. R. 2 W.	8,4; 1,4; 5,L-8
3. MISCELLANEOUS PROPERTY IN SECTION:	T. N. S., R. W.	
4. LOT NO., RECORDED PLAT:		
5. PRIVATE CLAIMS:		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, KENNETH J. OSTLING, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on JULY 13, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and or subsequent restoration:

B. Description of corner evidence found and or method applied in restoring or re-establishing corner:

- 8,4 - SET BY STANDARD SURVEY PROCEDURE TO IDENTIFY PROPERTY LINE AT ROAD R/W.
- 1,4 - SET BY STANDARD PROCEDURES FOR SUBDIVISION OF SECTION, TO MARK PROPERTY LINE OF P.A.S.
- 5,L-8 - FOUND AXLE SHAFT ON 1/4 LINE AT SHORE MULLETT LAKE AT NE CORNER OF GOV'T. LOT 2. FITS SECTION SUBDIVISION CORNERS.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


<u>8,4</u>	<u>1,4</u>	<u>5,L-8</u>
SET 5/8" ROD W/RLS CAP	SET 5/8" ROD W/RLS CAP	LEFT AXLE SHAFT IN PLACE
3" CEDAR N10°W 36.2'	4" W. BIRCH N40°W 5.4'	:: 7" W. BIRCH S32°W 4.06'
3" CEDAR N47°E 28.0'	4" W. BIRCH N82°E 9.4'	:: 14" W. SPRUCE S40°E 25.75'
∩ OF ROAD 33' SOUTH		

::NAIL W/DNR REFERENCE TAG

SIGNED BY Kenneth J. Ostling

DATE 2/16

SURVEYOR'S MICHIGAN REGISTRATION NO. 10068



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ CHEBOYGAN COUNTY

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET