

1999 CHEBOYGAN COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED
 FOR RECORD

00 JAN -3 PM 12:45

For corners in
 Cheboygan

(County)

Located In:

Corner Code #

1. Public Land Survey

T36N R 3W	A-7
T36N R 4W	M-7
T R	
T R	
S T R	
S T R	
S T R	
S T R	

2. Property Controlling
 in Section

3. Miscellaneous
 Property in Sec.

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Debbie Pappas
 CLERK/REGISTER
 CHEBOYGAN COUNTY MICHIGAN

MAR 03 2000

Register of Deeds Stamp & File Number
 SECTION

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Brian K. Fullford, in a field survey on Sept., 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

This corner is also designated as M-7 in T36N-R4W.

A. Description of original monument and accessories and/or subsequent restoration:

1840 Orig. Survey J. Mullett Set post 10" Hemlock S28°W 7 Lks 6" Spruce N77° 30 Lks	8" Spruce S12°E 32 Lks 14" Spruce N81°E 17 Lks Aug 1912 Sidney Main Emmet Co. Surveyor Fnd old wits reset Pine post 40" Pine stump S48°E 70' 6"	Sept. 1977 O. Doyle #7319 Set 3/4" pipe w/plug 6" W. Pine S5°E 6.25' 12" Jack Pine N36°E 10.39' 12" Jack Pine N65°W 6.77' Apr. 1980 J. Green RLS 15401 Fnd 3/4" pipe w/plug	6" W. Pine S5°E 6.25' 12" Jack Pine N36°E 10.39' 12" Jack Pine N65°W 6.77' July 1984 J. Green Rls 15401 Fnd 3/4" pipe No witnesses given
---	--	---	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" pipe with plug
 14" Jack Pine N34°E 10.39' with square tag
 11" W. Pine S5°E 6.4' with DNR Section tag
 13" Jack Pine N65°W 6.77' with square tag



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-7 Set 5/8" X 36" iron bar with remonumentation cap inside 3/4" pipe. Position is accepted as a careful and faithful perpetuation of the original corner.

14" J. Pine N34°E 10.39' w/sq tag
 11" W. Pine S5°E 6.35' Set tag 41099 also has DNR Section identification tag
 13" J. Pine N65°W 6.77' w/square tag
 7" Maple N87°E 12.04' Set tag 41099

Signed by B. K. Fullford
 Surveyor's Michigan License No. 41099

Date 12/17/99

