

1999 CHEBOYGAN COUNTY REMONUMENTATION  
 LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED  
FOR RECORD

00 JAN -3 PM 12:56

For corners in  
Cheboygan

(County)

Located In:

Corner Code #

1. Public Land Survey	T	36N	R	3W	B-3
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

*Deidy Pappasaki*  
 CLERK/REGISTER  
 CHEBOYGAN COUNTY MICHIGAN

MAR 03 2000

SECTION  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Brian K. Fullford, in a field survey on Sept., 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

Resurvey 1855  
 Set 1/4 Post  
 8" W. Birch N37°E 16 Lks.  
 28" W. Pine S5°W 9 Lks.

Sept. 1976 H. Fluharty RIs. #18223  
 Set 5/8" X 18" Re-rod w/RIs cap  
 Proportioned distance on line  
 5" R. Pine N06°E 17.30'  
 8" Tw. Maple S38°E 28.86'  
 13" R. Pine S47°W 54.86'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fnd Conc Mon w/U of M cap RLS #7319  
 8" R. Pine N7°E 17.2' with old scar no tag  
 15" R. Pine S46°W 54.70' with old tag  
 3" Maple clump S38°E 29'



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-3 Use existing concrete monument with U of M cap RLS #7319. Position is accepted as a careful and faithful perpetuation of the original corner.

8" Red Pine N7°E 17.18' Set tag 41099  
 15" Red Pine S46°W 54.70' w/old tag  
 10" Tw. Birch S24°W 31.08' Set tag 41099  
 17" Tw. Maple N70°E 43.00' Set tag 41099

Signed by *B. K. Fullford*  
 Surveyor's Michigan License No. 41099

Date 12/17/99

