

RECEIVED FOR RECORD

1999 CHEBOYGAN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

00 JAN -3 PM 12:42

For corners in Cheboygan

Table with columns: Located In: (County), Corner Code #, and rows for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

Handwritten signature: Vicky Pyszynski, CLERK/REGISTER CHEBOYGAN COUNTY MICHIGAN

MAR 03 2000

SECTION Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat 5. Private Claims

I, Brian K. Fullford, in a field survey on Sept. 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-L and rows 1-13, containing numbers 1-36 and a dot in cell 7B.

A. Description of original monument and accessories and/or subsequent restoration:

Table with 4 columns of survey data including dates (Mar. 1992, June 1994, Jan. 1998), descriptions (Resurvey, Set 1/2" Post, etc.), and distances (12" Hemlock S50°E 17 Lks., etc.).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fnd 1/2" iron bar w/cap 16041 Fnd old scribed cedar post laying down by 1/4 Section corner 15" Poplar N74°E 14.91' with tag 10" Maple S7°W 4.05' with tag 16041 and DNR Section identification tag 12" Birch N68°W 4.2' No tag



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-7 Replaced 1/2" bar & cap 16041 with 5/8" X 36" iron bar & remonumentation cap. Position is accepted as a careful and faithful perpetuation of the original corner.

- 8" Birch N51°E 25.46' Set tag 41099
15" Poplar N74°E 14.91' w/tag
10" Maple S7°W 4.05' w/tag 16041 & DNR Section identification tag
12" Birch N68°W 4.25' Set tag 41099

Signed by [Signature] Surveyor's Michigan License No. 41099

Date 12/17/99

