

Cheboygan 1999

1998

SECTION

CHEBOYGAN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Cheboygan

Located In: Corner Code #

1. Public Land Survey

T36N R 3W D-1 D-13

2. Property Controlling in Section

S T R

3. Miscellaneous Property in Sec.

S T R

RECEIVED FOR RECORD 1-8-99 at 8:59 O'Clock A.M.

James Spray

CLERK/REGISTER CHEBOYGAN COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat 5. Private Claims

I, Brian K. Fullford, in a field survey on June 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-L and rows 1-13. A dot is marked in cell D-1.

A. Description of original monument and accessories and/or subsequent restoration:

1840 John Mullett Original Survey Set 1/4 post 7" Maple N 25° W 47 lks 6" Beech N 62° E 38 lks

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fnd 5/8" pipe under Asphalt Rd. 7' North of Centerline Road 28' +/- West of Centerline Two-track to North 42' +/- West of Centerline Two-track to South P. Pole #1583 N 18° E 52.54' w/ old tag no id 13" R. Pine S 9° E 51.07' w/ old tag no id 12" R. Pine S 22° W 54.25' w/ old tag no id



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-1 Replaced 5/8" pipe with 5/8" rebar with remonumentation cap in monument box, and position is accepted as a careful and faithful perpetuation of the original corner.

P. Pole #1583 N 18° E 52.54' w/ tag 15" R. Pine S 50° E 76.99' Set tag 41099 13" R. Pine S 9° E 51.07' w/ tag 12" R. Pine S 22° W 54.25' w/ tag

NOTE: THIS CORNER IS ALSO DESIGNATED CODE D-13 IN T37N-R3W.

Signed by [Signature] Surveyor's Michigan License No. 41099

Date 11/23/98

