

1998
CHEBOYGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION _____
Cheboygan
(County)

Located In:	Corner Code #
T 36N R 3W	E-1 ✓
T 37N R 3W	E-13
T _____ R _____	_____
T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____

RECEIVED FOR RECORD 1-8-99
at 9:01 O'Clock A M
Joanne Spray
CLERK/REGISTER
CHEBOYGAN COUNTY, MICHIGAN
Register of Deeds Stamp & File Number

1. Public Land Survey
2. Property Controlling in Section
3. Miscellaneous Property in Sec.
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Brian K. Fullford, in a field survey on June, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.


A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

1840 John Mullett Original Survey Set post 6" Pine N 7° W 12 lks (7.92') 8" B. Oak N 32° E 68 lks (44.88')	Sept 1976 Herbert Fluharty #18223 Fnd 1" pipe @ intersection brush line N & S and Old Trail E & W 9" Oak S 20° W 16.96' 11" Oak N 60° W 40.90' 7" Oak N 52° E 34.71'
---	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fnd 1" pipe on N & S brush Line
11" Triple Oak N 52° E 34.70' w/ blaze
14" R. Pine S 16° E 36.46' w/ tag & blaze
13" Oak S 20° W 16.90' w/ blaze
14" Oak N 60° W 40.98' w/ blaze



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-1 Placed 5/8" rebar with remonumentation cap inside pipe, and position is accepted as a careful and faithful perpetuation of the original corner.

11" Triple Oak N 52° E 34.70'	Set tag 41099
14" Red Pine S 16° E 36.46'	w/ old tag
13" Oak S 20° W 16.90'	Set tag 41099
14" Oak N 60° W 40.98'	Set tag 41099

NOTE: THIS CORNER IS ALSO DESIGNATED AS CODE E-13 IN T37N-R3W.

Signed by *B. K. Fullford*
Surveyor's Michigan License No. 41099

Date 11/23/98

