

SURVEYING
REMONUMENTATION
JAN 6 1999

SECTION

1998
CHEBOYGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Cheboygan
(County)

Located In: Corner Code #

1. Public Land Survey	T 36N R 3W	G-1
	T 37N R 3W	G-13
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

RECEIVED FOR RECORD 1-8-99
at 9:06 O'Clock A.M.
Jeanne Spray
CLERK/REGISTER
CHEBOYGAN COUNTY, MICHIGAN
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Brian K. Fullford, in a field survey on June, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5			4		3		2			1
3												
4	7	8			9		10		11			12
5												
6	18	17			16		15		14			13
7												
8	19	20			21		22		23			24
9												
10	30	29			28		27		26			25
11												
12	31	32			33		34		35			36
13												

A. Description of original monument and accessories and/or subsequent restoration:

1840 John Mullett Original Survey Set Post 9" Hemlock N 24° W 3 lks 8" Hemlock N 65° E 33 lks	1970 Doyle Civil Engineers #7319 Fnd 1" pipe W. Pine S 75° 30' E 50.36' W. Pine S 74° 30' W 23.69' W. Pine N 17° 30' E 46.45'
---	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fnd Conc Mon w/U of M cap & RLS #7319
13" R. Pine N 15° E 46.38' w/ old tag
13" R. Pine S 77° E 50.07' w/ old tag
13" R. Pine S 72° W 23.68' w/ old tag



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-1 Use existing concrete monument with U of M cap & RLS #7319, and position is accepted as a careful and faithful perpetuation of the original corner.

13" R. Pine N 15° E 46.38'	w/ old tag
13" R. Pine S 77° E 50.07'	w/ old tag
8" Poplar S 23° W 28.59'	Set tag 41099
13" R. Pine S 72° W 23.68'	w/ old tag

Note: THIS CORNER IS ALSO DESIGNATED CODE G-13 IN T37N-R3W.



Signed by *B. K. Fullford*
Surveyor's Michigan License No. 41099

Date 1/23/98